

900-Series

Modular Distribution System

- Versatile Low-noise Distribution
- Up to 30 channels available from each rack
- Ultra low noise and EMC profile
- Flexible configuration and mounting arrangements
- Auto changeover units for fully redundant switching ensures safe, continuous 24/7 operation
- Wide range of modules available including reference frequencies, 1PPS timing and a variety of timecodes



The 900-series distribution amplifiers are for local distribution of time code signals, 1PPS timing signals, sinewave reference frequency to multiple outputs, up to 30 per cabinet.

900-Series Overview

The 900 series is a range of high-reliability modules which are used to build versatile signal distribution systems. The use of ultra-low-noise Power Supplies, enclosed module construction and co-axial cable for interconnections means that the units have excellent noise, emissions and immunity characteristics. The mainframe is suitable for 19" rack, desktop or wall mounting.

Typical applications are in installations where 'round the clock' reliability is a must. Examples include manufacturing plants for items such as mobile communications equipment and cellular base stations, both military and commercial. More generally the 900 series has applications in development laboratories, support workshops and calibration areas.

The 900 series units can also be found in many satellite ground stations, running up/down links from the Poles to the Tropics.

The 900 series can be widely configured with distribution of a variety of reference frequencies, 1PPS timing and various timecodes.

Up to 30 individually buffered outputs at +13 dBm (1V rms in 50 ohm) is available from one 3U high cabinet.

Continuous un-interrupted operation is assured via autochangeover input modules, allowing redundant frequency sources to be used. Dual, hot-swappable power supply modules may be fitted to provide power redundancy.

A 5 MHz to 10 MHz frequency doubler module provides good quality output signals without the need to use synthesizers or tracking oscillators.

All modules have built in test and can detect faults down to individual output level.

Alarms are consolidated in the rack PSU module and transmitted by relay output. Automatic signal source changeover is provided by some modules. This facility can be controlled manually by a front panel rotary switch, or remotely via a commercially available I/O to Ethernet adapter.





Input Modules

910D - Input Conditioning/Splitter Module

Input freq. range: 1 MHz to 10 MHz Input level: 0 dBm to +13 dBm (adjustable) Input connector: 1 x Input, N-Type

Output connector: 6 x SMA (Signal split to five output modules, 1 spare for local cascade connection)

Alarm: Input level and Output level fault indicators, with alarm threshold adjustment on front panel

980A - RF Auto-Changeover Module

Input freq. range: 1 MHz to 10 MHz **Input level:** 0 dBm to +13 dBm

Input connector: 2 x BNC (Master and Slave inputs)

Output connector: 3 x BNC (Buffered Master, Buffered Standby, and Source-in-use) Indicators: Input level fault indicators, with alarm threshold adjustment on front panel + source in use

Remote control: TTL remote control interface and status readout, 'D-sub' connector. Front panel manual override switch

980B - Timecode Auto-Changeover Module

Input connector: 2 x BNC (Master and Slave inputs)

Output connector: 3 x BNC (Buffered Master, Buffered Standby, and Source-in-use) **Indicators:** Input level fault indicators, with alarm threshold adjustment on front panel + source in use

Remote control: TTL remote control interface and status readout, 'D-sub' connector. Front panel manual override switch

980C - 1PPS Auto-Changeover Module

Input signal: 1PPS; TTL-levels in 50 ohm Input connector: 2 x BNC (Master and Slave inputs)

Output connector: 3 x BNC (Buffered Master, Buffered Standby, and Source-in-use) **Indicators:** Input level fault indicators, with alarm threshold adjustment on front panel + source in use

Remote control: TTL remote control interface and status readout, 'D-sub' connector. Front panel manual override switch

RF (1 to 10 MHz) Output Modules

Common

All output modules receive normally their input reference signal from the Input / Splitter module 910D or the 980 Changeover module.

Input signal connector: 1x SMA

909B - Standard Sinewave Output Module
Output level: specify at time of order
Output connector: 6 x BNC

Indicators: Individual output alarm indicators and user adjustable alarm threshold level

G919A - Hi-level Sinewave Output Module

Output level: up to +19 dBm 50 ohm

(adjustable)

Output connector: 3 x BNC

920B - 5 to 10 MHz Frequency Doubler Sinewave Output Module

Input freq.: 5 MHz Output freq.: 10 MHz

Output level: +13 dBm in 50 ohm Output connector: 6x BNC

922A/B/C - TTL RS422 Output Module

Input freq.: A and C (1 to 10 MHz), B (1PPS)
Input signal.: A and C (TTL), B (RS422)
Output signal: A and B (RS422), C (TTL)
Output connector: 6x BNC

Timecode Output Modules

909E - Timecode Output Module

Input: 1x SMA (from input module 910D) **Timecode:** modulated codes as presented at input

Output level: up to +13 dBm in 50 ohm (adjustable)

Output connector: 6 x BNC

930A - Universal Fiber Transceiver Module

Two channel copper/fibre transceiver module for timecodes and/or logic signals

Input: 2x BNC (TTL-levels), 2x opto (ST)

Timecode: IRIG-A, IRIG-B, NMEA, or any logic signal to 500 kHz

Output level: TTL-levels in 50 ohm (BNC)
Output connector: 2x Opto (ST-connector)

2x BNC logic outputs

Indicator: Front-panel input/output fault monitor

Power Supply Module

911 - Power Supply Module

AC mains: 115 or $230V \pm 10\%$ (45 to 66 Hz) DC output: via ribbon connector +/- 14V, 1A

nominal, to other modules in cage

Indicators: Low voltage warning for internal DC voltages.

Alarm input: Module alarm signal input via power ribbon cable from all cage modules Alarm output: Cage alarm relay on isolated

BNC connector (normally closed)

General Specifications

Environmental Data

Operating Temp: 0°C to +50°C **Storage Temp:** -40°C to +70°C **Safety:** EN 61010-1, EN 60950, CE **EMC:** EN 50081-1, EN50081-2, CE

Dimensions and Weight

Rack Width \times Height \times Depth: $483 \times 134 \times 350 \text{ mm } (19" \times 5.3" \times 13.8")$ Module Width \times Height \times Depth: $60 \times 130 \times 230 \text{ mm } (2.4" \times 5.1" \times 9")$ Weight: 4.0 kg (mainframe only) to 11.0 kg (fully populated)

Ordering Information

900A: 19" mainframe

909B: Standard sinewave output module

909E: Timecode output module

910D: Input splitter module911D: 230 V AC mains power module

911E: 115 V AC mains power module 919A: Hi-level sinewave output module 920B: 5 to 10 MHz frequency doubler module

922A: 10 MHz TTL to R\$422 **922B:** 1PPS TTL to R\$422 **922C:** 10 MHz R\$422 to TTL

930A: Universal fiber transceiver module
980A: RF auto-changeover module
980B: Timecode auto-changeover module
980C: 1PPS auto-changeover module

Included with Shipment

Mains cable (to power module 911)
User manual
2 year warranty